

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20091-00-017  
Spot: W2NWNW Sec/Twnshp/Rge: 21-14S-10W  
660 feet from N Section Line, 330 feet from W Section Line  
Lease Name: VOPAT A OWWO Well #: 1  
County: ELLSWORTH Total Vertical Depth: 2919 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2048		
SURF	8.625	225		200 SX CMT
PROD	4.5	2519		200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2010 11:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: SEE BELOW. PERFORATIONS WERE NOT ON CP-1, GOT THAT INFO FROM KEN BUEHLER ON LOCATION.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/20/2010 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP AT 2048' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1200', 850' AND 275'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 850' AND PUMP 35 SXS CEMENT. PULL TUBING TO 275' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON CASING - ATTEMPT PUMPING - PRESSURED UP TO 500#'S - STOPPED. PULL TUBING OUT AND TOP OFF. CONNECTED ONTO TO SURFACE CASING AND PUMPED CEMENT THAT LEAKED OUT INTO CELLAR, AFTER PRESSURING UP.

Perfs:

Top	Bot	Thru	Comments
2146	2166	CSG	
2098	2102	CSG	

RECEIVED  
AUG 17 2010  
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. PERF TECH TICKET #7386. ALLIED CEMENT TICKET #41674.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

JK