

\$124.70

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26040-00-00  
Spot: S2SWNWSE Sec/Twnshp/Rge: 16-13S-20W  
1385 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: KINDERKNECHT Well #: 2  
County: ELLIS Total Vertical Depth: 3838 feet

Operator License No.: 6509  
Op Name: CLARK, JIM D. DBA CLA-MAR OIL, CO  
Address: PO BOX 1197  
HAYS, KS 67601

String Size Depth (ft) Pulled (ft) Comments  
SURF 8.625 217

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/2010 4:00 PM  
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC  
Proposal Rcvd. from: DOUG BUDIG Company: CLA-MAR OIL, COMPANY Phone: (785) 625-3863

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE  
Date/Time Plugging Completed: 10/10/2010 5:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 1525' w/25 sxs.  
2nd. Plug at 725' w/100 sxs.  
3rd. Plug at 270' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

12/07/10  
201060310

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

RECEIVED Form CP-2/3

NOV 03 2010

11-03-10  
KCC WICHITA

OCT 28 2010