

# 143.98

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20912-00-00  
Spot: SESESE Sec/Twnshp/Rge: 14-22S-18W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: EIKMEIER Well #: 2  
County: PAWNEE Total Vertical Depth: 4430 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	301		WITH 250 SX CMT
PROD	5.5	4387	1530	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2010 1:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 10/06/2010 3:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PRESSURED 5 1/2" TO 500 PSIG. 1ST PLUG AT 1160' WITH 100# HULLS - 15 SX GEL - 50 SX CMT. 2ND PLUG AT 340' WITH 100# HULLS - 50 SX CMT. 3RD PLUG AT 40' WITH 55 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4118	4118		

INVOICED  
DATE 12/07/10  
IV. NO. 2011060288

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Steve Durrant

RECEIVED  
OCT 22 2010  
KCC DODGE CITY

(TECHNICIAN)  
RECEIVED  
OCT 27 2010  
KCC WICHITA