

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20195-00-00  
Spot: SESESW Sec/Twnshp/Rge: 17-17S-3W  
350 feet from S Section Line, 3137 feet from E Section Line  
Lease Name: REESE COMMUNITY Well #: 1  
County: MCPHERSON Total Vertical Depth: 3478 feet

Operator License No.: 6306  
Op Name: TOM BROWN CONSTRUCTION, INC.  
Address: 54921 RIVERVIEW DR  
ASTOR, FL 32102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	12	100		76SXS
COND	7	100		76 SX
PROD	7	3476		75SXS

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2010 10:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: KELSO CASING Company: \_\_\_\_\_ Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2010 3:15 PM KCC Agent: SHANE JONES

Actual Plugging Report:

8/15/2010 KELSO'S LAID OUT THE WELL, DROPPED SAND FOR BOTTOM PLUG AND PERFORATED 7" @ 350'. 8/16/2010 KELSO'S TAGGED SAND @ 3420' AND CAPPED IT WITH 7 SXS CEMENT. THEY HAD SCHULZ OUT TO DIG OUT WELL HEAD. THEY FOUND THE WELL HAD A 6' X 8' CEMENT CELLAR. ONCE THEY GOT THE CELLAR DUG DID NOT FIND AN SURFACE HEAD. FURTHER CLEANING AND DIGGING FOUND THE 12" HAD BEEN ORANGE PEELED AND WELDED TO THE 7". THE CELLAR FLOOR HAD BEEN PURED TO THE TOP OF THE 12" . KELSO'S CUT A WINDOW IN THE 12" AND RAN 2 7/8" TUBIN INSIDE THE 7" TO 360'. COPELAND TIED ON AND BROKE DIRCULATION WITH WATER. THEY SWITCHED TO CEMENT. THEY PUMPED APPROX 250 SXS BEFORE RAN OUT OF WATER. WHILE WAITING ON THE WATER TRUCK TO GO GET MORE WATER. THE OTHER TRUCK FINISHED SUCKING OUT THE CELLAR. NOTICED WE HAD JUST STARTED TO CIRCULATE CEMENT UP THE BACKSIDE WHEN WE HAD RAN OUT OF WATER. WATER TRUCK RETURNED AND STARTED PUMPING DOWN BACKSIDE AGAIN GOT GOOD CEMENT CIRCULATED UP THE BACKSIDE. THEY THEN OPENED THE BACKSIDE OF THE 7" HEAD AND PUMPED ANOTHER 35 SXS AND CIRCULATED TO SURFACE. KELSO'S PULLED TUBING AND COPELAND TOPPED OFF WELL HEAD WITH 10 SXS. THEY FINISHED @3:15 PM. THEY USED A TOTAL OF 295 SXS OF 60/40 POS W/ 4% GEL TK #34584. 8/18/2010 I CHECK TOP PLUG. IT WAS DOWN ABOUT 4' ON THE BACKSIDE AND ABOUT 25' DOWN THE INSIDE OF THE 7". I SPOKE TO DENNY WALKER AND HE WILL HAVE SOME SLURRY BROUGHT OUT AND TOP IT OFF.

Perfs:

Top	Bot	Thru	Comments
3476	3478	OH	


RECEIVED  
SEP 01 2010  
KCC WICHITA

Remarks: PLUGGED BY COMMISSION ORDER. WELL HAS BEEN DOWN MORE THAN 10 YEARS. CASE CLOSED  
8/16/2010 SJ

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)