

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-00945-00-00
Spot: NWNWSWNW Sec/Twnshp/Rge: 1-16S-4W
3922 feet from S Section Line, 4976 feet from E Section Line
Lease Name: RYDING Well #: 5
County: SALINE Total Vertical Depth: 3434 feet

Operator License No.: 6306
Op Name: TOM BROWN CONSTRUCTION, INC.
Address: 54921 RIVERVIEW DR
ASTOR, FL 32102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	365		
PLG3	5.5	3432		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2010 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2010 12:15 PM KCC Agent: SHANE JONES

Actual Plugging Report:

8/12/2010 KELO'S DROPPED SAND THIS MORNING LET SET FOR 2 HRS. THEY WENT BACK IN AND TAGGED CEMENT @ 3380', AND THEY CAPPED IT WITH 5 SX. LOG TECH OUT AND PERFORATED AT 415'. KELSO'S RAN 2" DOWN TO 420' AT 12:15 WE ARE WAITING ON COPELAND. BULK TRUCK FINALLY ARRIVED @ 1:45 PM. COPELAND TIED ON TO TUBING AND TRIED TO CIRCULATE WATER. THE PACKING IN THE CASING HEAD LEAKING. THEY TRIED REVERSING AND PUMPED DOWN THE BACKSIDE TO CIRCULATE UP THE 5.5". THEY DID NOT GET ANY CIRCULATION. THEY WILL NEED TO CUT OFF HEAD AND RUN 1" DOWN BACKSIDE TO 415'. WILL TRY TO PLUG IN THE MORNING STARTING @ 8:30 AM. I ARRIVED AT 8:30 AM THEY ARE STILL WORKING ON CUTTING THE BRAIDEN HEAD OFF. SCHULZ WELDONG CUT OFF BRADEN HEAD. KELSO'S RAN 1" DOWN TO 408'. THEY TIED ON AND CIRCULATED DOWN TO 420' THEY PULLED BACK UP TO 408'. COPELAND TIED ON AND BROKE CIRCULATION WITH WATER THEN SWITCHED TO CEMENT. THEY PUMPED 80 SX AND CIRCULATED CEMENT TO SURFACE ON BACKSIDE. KELSO'S THEN PULLED THE 1" AND RAN 2" DOWN THE 5.5" TO 420'. COEPLAND TIED ON AND BROKE CIRCULATION WITH WATER AND THEN SWITCHED TO CEMENT. THEY PUMPED 40 SXS AND CIRCULATED TO SURFACE. KELSO'S PULLED TUBING, AND COPELAND TOPPED OFF THE WELL WITH 5 SXS. THEY FINISHED UP AT 12:15 PM. THEY USED 125 SXS OF 60/40 POS W/4% GEL. TK #34576.


Perfs:

Top	Bot	Thru	Comments
3432	3434	OH	

Remarks: PLUGGED BY COMMISSION ORDER FOR FAILURE TO FILE A CP-111. WELL HAD BEEN DOWN FOR OVER 10 YEARS. CASE CLOSED #0924862 8/13/2010 SJ

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

RECEIVED
AUG 19 2010
KCC WICHITA

Form CP-2/3

JSK