

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20536-00-01  
Spot: NWSWSWNE Sec/Twnshp/Rge: 23-14S-11W  
3001 feet from S Section Line, 2476 feet from E Section Line  
Lease Name: SMALL A Well #: 2  
County: RUSSELL Total Vertical Depth: 2183 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221	0	160 SX
PROD	5.5	2182	0	50 SX

Well Type: EOR UIC Docket No: E17785.1 Date/Time to Plug: 10/07/2010 10:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Perf 1200' - 500' - 200'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/07/2010 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 1936' - pumped 100 sxs cement with 300# hulls.  
Pulled tubing to 936' - pumped 85 sxs cement with 100# hulls - cement circulated.  
POOH. Hooked to casing and pumped 10 sxs cement to load casing and 30 sxs to circulate out the Braden head.

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKE #4350.

Plugged through: TBG

RECEIVED  
OCT 18 2010  
KCC WICHITA

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

Form CP-2/3

OCT 08 2010