

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20531-00-01
Spot: NWNENWSE Sec/Twnshp/Rge: 23-14S-11W
2363 feet from S Section Line, 1789 feet from E Section Line
Lease Name: SMALL Well #: 3
County: RUSSELL Total Vertical Depth: 2160 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211	0	160 SX
PROD	5.5	2159	0	60 SX

Well Type: EOR UIC Docket No: E26804.1 Date/Time to Plug: 10/05/2010 9:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 1200' - 500' - 200'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2010 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 1936' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 936' - pumped 85 sxs cement with 100# hulls - cement circulated.
POOH. Hooked to Braden head and pumped 5 sxs cement.
Max. P.S.I. 150#.
Hooked to casing and pumped 5 sxs cement.
Max. P.S.I. 200#.

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKE #4547.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN) CM

RECEIVED

OCT 12 2010

Form CP-2/3

KCC WICHITA

OCT 07 2010