

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20241-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 24-14S-11W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease Name: STOPPEL Well #: 2  
County: RUSSELL Total Vertical Depth: 2847 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	295	0	275 SX
PROD	4.5	2846	0	75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/21/2010 10:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Perf: 1300' - 500' - 290'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/21/2010 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2600' - pumped 100 sxs cement with 300# hulls.  
Pulled tubing to 1150' - pumped 140 sxs cement with 200# hulls.  
Cement circulated out 4 1/2" casing and the Braden head.  
POOH. Filled casing with 20 sxs cement.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3940.

Plugged through: TBG

District: 04

Signed R. A. D. K. D.  
(TECHNICIAN) CM

RECEIVED  Form CP-2/3

NOV 01 2010

KCC WICHITA

OCT 22 2010