

B 97.60

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21085-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 34-18S-2E
2977 feet from S Section Line, 4686 feet from E Section Line
Lease Name: SCULLY A Well #: 1-34
County: MARION Total Vertical Depth: 3003 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	158		
PROD	5.5	2989		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/08/2010 8:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2010 4:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:


10/7 AMERICAN ENERGIES DUG OUT WELL HEAD. THEY CUT A SLOT IN THE 8 5/8" TO RUN 1" DOWN THE BACKSIDE. AMERICAN ENERGIES FOUND A BRIDGE IN THE 5.5" @100'. THEY DRILLED OUT ABOUT 15' BRIDGE AND THEN GOT ALL THE WAY TO BOTTOM. THEY DROPPED SAND FOR BOTTOM PLUG. 10/8 THE TAGGED SAND @ 2862' AND CAPPED W/5 SXS. THEY RAN 1" DOWN THE BACKSIDE AND TAGGED @ 75' SOLID. THEY RAN TUBING DOWN THE 5.5" TO 250'. COPELAND TIED ON AND CIRCULATED THE 5.5" WITH WATER THEN SWITCHED TO CEMENT, CEMENT CIRCULATED TO THE SURFACE OF THE 5.5". THEY ALSO GOT CIRCULATION UP THE BACKSIDE. TIED ON TO THE 1" AND CIRCULATED CEMENT TO SURFACE. AMERICAN ENERGIES PULLED THE TUBING AND COPELAND TOPPED OFF THE WELL. COPELAND USED 145 SXS 60/40 POS W/4% GEL TK #36781. 10/9 I TAGGED TOP PLUG @ 12' DOWN. THE BACK SIDE APPEARS TO BE FULL. I CONTACTED TRAVIS W/AMERICAN ENERGIES. TRAVIS SAID THEY WOULD DRY SACK TO CUT OFF POINT AND THEN BURY. (The well has an approved TA because operator had CP-111 with wrong information for well. Has all been corrected. CP-111 should have been denied. Operator admitted well has not produced since they have owned it. T-1 from Randon to American Energies said well was producing.

Perfs:

Inv. dt: 12/15/10
Inv. #: 201106285

Remarks:
Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

RECEIVED

Form P-2/3

OCT 15 2010

KCC WICHITA

1/84