

\$ 97.66

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20379-00-00
Spot: NENWSE Sec/Twnshp/Rge: 20-19S-1E
2268 feet from S Section Line, 1662 feet from E Section Line
Lease Name: WESLEY DUERKSEN Well #: 1
County: MARION Total Vertical Depth: 3005 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	198		100 SXS CMT
PROD	4.5	2922		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/22/2010 10:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: TRAVIS HAMM Company: _____ Phone: (620) 628-4424

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/25/2010 10:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

10/20/2010 AMERICAN ENERGIES DROPPED SAND. 10/21/10 AMERICAN ENERGIES TAGGED SAND @ 2744' AND CAPPED W/5 SXS. THEY THEN RAN 1" DOWN BACKSIDE TO 250'. THEY RAN 2 7/8" DOWN TO 250' INSIDE THE 4.5". 10/22/10 COPELAND TIED ON TO THE 1". COPELAND PUMPED 80 SXS DOWN 1" TO CIRCULATE TO SURFACE. THEY THEN TIED ON TO THE 2 7/8" AND BROKE CIRCULATION WITH WATER. ONCE HAD CIRCULATION SWITCHED TO CEMENT AND CIRCULATED 30 SXS TO SURFACE. AMERICAN ENERGIES THEN PULLED THE TUBING, AND COPELAND TOPPED OFF THE WELL W/5 SXS. TK # 36646 USED 115 SXS 60/40 POS W/4% GEL. 10/25/10 I CHECKED THE TOP PLUG FINDING IT DOWN 165' INSIDE THE 4.5" AND DOWN 75' ON THE BACKSIDE. THE HOLE IS DRY. COPELAND OUT AND TOPPING OFF WELL WITH 42 SXS 60/40 POS W/4% GEL TO SURFACE TK #35157. 10/26/10 CHECKED TOP PLUG AT SRUFACE.


Perfs:

Top	Bot	Thru	Comments
3299	3300	CSG	
2851	2857	CSG	
0	0		

Imv dt: 12/15/10
Imv #: 2011060285

Remarks: PBTD 2925'
Plugged through: TBG

District: 02

Signed 

(TECHNICIAN)
RECEIVED

NOV 03 2010

Form CP-2/3

KCC WICHITA

✓ SK