

\$106.37

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19238-00-00  
Spot: NWSWNWSW Sec/Twnshp/Rge: 20-33S-3E  
1663 feet from S Section Line, 4951 feet from E Section Line  
Lease Name: WEST RAINBOW BEND UNIT Well #: 15  
County: COWLEY Total Vertical Depth: 3273 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		225 SX
PROD	5.5	3236	1550	100 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/13/2010 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: Company: KIVETT PLUGGING & PIPE Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/15/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3180'. DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1550', LAYED DOWN CASING. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 4-15-2010. CONSOLIDATED CEMENT TICKET #24112.

Perfs:

Top	Bot	Thru	Comments
3236	3273	OH	BARTELSVILLE

Dr. dt: 12/15/10  
Inv. #: 2011060259

Remarks:

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

RECEIVED  
AUG 12 2010  
KCC WICHITA

Form CP-2/3

✓SK