

93.44

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-02088-00-00
Spot: SWNESWSE Sec/Twnshp/Rge: 6-34S-6E
724 feet from S Section Line, 1695 feet from E Section Line
Lease Name: WALDSCHMIDT Well #: 1
County: COWLEY Total Vertical Depth: 2875 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	81		
PROD	5.5	2850	478	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/28/2010 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: _____ Company: KIVETT PLUGGING & PIPE Phone: (560) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/28/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
RJH ON WIRELINE SET CIBP @ 1950', DUMP BAILED 5 SXS CEMENT ON TOP. CUT 5.5" CASING @ 478', LAYED DOWN 5.5" CASING. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 165 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 4-28-2010. CONSOLIDATED CEMENT TICKET #24376.

Perfs:

Top	Bot	Thru	Comments
2790	2791	CSG	

Inv. dt: 12/15/10
Inv. #: 2011060259

Remarks:
Plugged through: TBG

District: 02 Signed Duane Krueger
(TECHNICIAN)

RECEIVED
AUG 12 2010
KCC WICHITA