

\$ 145.67

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20347-00-00
Spot: NENE Sec/Twnshp/Rge: 20-28S-9W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: HAUSER Well #: 2
County: KINGMAN Total Vertical Depth: 4482 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	288		250 sx cement
PROD	5.5	4465		175 sx cement

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/10/2010 12:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: GEORGE Company: GRESSEL OILFIELD SERVICE Phone: (316) 524-1225

Proposed Plugging Method: TUBING STUCK IN HOLE. SHOT LOOSE AT 2480'. SET CIBP 2478 AND CAP WITH 2 SKS OF CMT. PERF AND CIRC 50 SKS CMT AT 1450', 950'. CIRC CMT FROM 340-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2010 4:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:
SET CIBP AT 2478' AND CAPPED WITH 5 SKS OF CMT. PERFED THE CASING AT 1450' AND 980', AND 340'. RAN TUBING TO 1450' AND SPOTTED 40 SKS OF CMT. PULLED TUBING TO 980' AND SPOTTED 50 SKS OF CMT. PULLED TUBING OUT OF THE HOLE AND TIED ON TO THE CASING AND PUMPED 185 SKS OF CMT. GOT COLOR BUT NO CMT. ON 8-20-2010 THE CASING WAS CUT OFF AND 85 SKS OF CMT WAS PUMPED IN THE 5.5 AND THE ANNULAS.

Perfs:

Top	Bot	Thru	Comments
4369	4374		Viola

Inv. dt: 12/15/10
Inv. #: 2011060294

Remarks: COPELAND CMT COMMON AND 60/40 4% GEL.
Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)

RECEIVED

OCT 28 2010

KCC WICHITA

Form CP-2/3

JK