

#128.44

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23689-00-00  
Spot: SENENWSE Sec/Twnshp/Rge: 10-6S-25W  
2250 feet from S Section Line, 1602 feet from E Section Line  
Lease Name: SLIPKE Well #: 1-10  
County: GRAHAM Total Vertical Depth: 3951 feet

Operator License No.: 31930  
Op Name: BLUE RIDGE PETROLEUM CORPORATI  
Address: PO BOX 1913  
ENID, OK 73702

String Size Depth (ft) Pulled (ft) Comments  
SURF 8.625 343

Well Type: DH UIC Docket No: Date/Time to Plug: 10/30/2010 5:00 PM  
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.  
Proposal Rcvd. from: RICK Company: BLUE RIDGE PETROLEUM CORPO Phone: (580) 242-3732

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE  
Date/Time Plugging Completed: 10/30/2010 6:15 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 2200' w/25 sxs.  
2nd. Plug at 1400' w/100 sxs.  
3rd. Plug at 400' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

INVOICED  
DATE 12/07/10  
INV. NO. 2011060787

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed Ed Schumacher

(TECHNICIAN)

RECEIVED

NOV 03 2010

KCC WICHITA

Form CP-2/3

NOV 01 2010