

127.73

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21229-00-00
Spot: SENE Sec/Twnshp/Rge: 30-9S-22W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: FARRELL A Well #: 3
County: GRAHAM Total Vertical Depth: 3930 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2255 S WADSWORTH, STE 205
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290	0	200 SX
T1	2	3875		
DVT		1969		
PROD	5.5	3917	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2010 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN CURLEY Company: VENTURE RESOURCES, INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
DV Tool at 1969' w/600 sxs cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2010 10:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 5 1/2" - pumped 425 sxs cement with 500# hulls - full.
Tied onto backside - pumped 10 sxs cement - full - shut in.

Perfs:

Top	Bot	Thru	Comments
3851	3856		LANSING
3751	3759		LANSING

DM-dt: 12/15/10
DM-#: 2011060256

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 02 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.-TICKET #18024.

Plugged through: CSG

District: 04

Signed

Marvin Mills

(TECHNICIAN)

CM

JUL 01 2010

CITIES SERVICE CO
 700 SUTTON PLACE
 WICHITA, KS 67202
 CONTR EMPHASIS OIL OPER

#3 FARRELL "A"
 CTY GRAHAM

30-9-22W
 C SE NE

GEOL FIELD RED LINE NW

E 2405 KB CM 4/23/80 CARD ISSUED 5/22/80 IP P 46 B0 & 155 BWPD
 LANS 3751-3856 OA

+	+	+
+	+	+
+	+	+

API 15-065-21,229

SMP	TOPS	DEPTH	DATUM
ANH		1943	+ .462
HEEB		3627	-1222
TOR		3650	-1245
LANS		3662	-1257
BKC		3894	-1489
MARM		3923	-1518
RTD		3930	-1525

8-5/8" 290/200sx, 5 1/2" 3917/100sx
 DV TOOL @ 1969/600sx

DST (1) 3751-62 (LKC)/30-30-30-60, 536'
 GIP, REC 31' HQCM 189' MDY GSY 0,
 100' o (GR 35°), 26 MCY GCSW, SIP
 668-668#, FP 52-94/94-146#, BHT 92°

DST (2) 3779-3815 (LKC)/30-45-45-90,
 150' MSW, SIP 460-460#, FP 31-52/
 63-105#, BHT 108°

DST (3) 3810-34 (LKC)/15-30-45-60,
 217' M, 124' MSW, SIP 957-585#, FP
 105-157/167-168#, BHT 100°

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)