

#145.86

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21557-00-00
Spot: N2NENE Sec/Twnshp/Rge: 30-33S-6W
4950 feet from S Section Line, 600 feet from E Section Line
Lease Name: PHIL Well #: 1-30
County: HARPER Total Vertical Depth: 4488 feet

Operator License No.: 4941
Op Name: UNION VALLEY PETROLEUM CORPOR
Address: 10422 PINTO LN
ENID, OK 73701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4430		
SURF	8.625	218		175 SX CMT.
PROD	4.5	4488	3210	225 SX CMT.

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/01/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: SET CIBP 50 FEET ABOVE TOP PERFS AND CAP WITH 5 SKS OF CMT. RECOVER CASING. SPOT 35 SKS 1100', 35 SKS 700' CIRC CMT FROM 270-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/01/2010 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE CIBP WAS SET AT 4430', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3210 AND PULLED TO 1100'; WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 270', WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4481	4488	CSG	

Sm. dt: 12/15/10
Sm. #: 2011060253

Remarks: QUALITY WELL SERVICE. 60/40 4% GEL

Plugged through: CSG

District: 02

RECEIVED
SEP 27 2010
KCC WICHITA

Signed _____

[Signature]
(TECHNICIAN)

JK