

\$ 283.21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-00049-00-00
Spot: SWSE Sec/Twnshp/Rge: 13-34S-37W
665 feet from S Section Line, 1714 feet from E Section Line
Lease Name: CUNNINGHAM ESTATE Well #: 1-13
County: STEVENS Total Vertical Depth: 8714 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5190		WITH 2 SX CMT
CIBP		6650		
SURF	8.625	1780		WITH 800 SX CMT
PC		3308		WITH 500 SX CMT
PC		5760		WITH 750 SX CMT
PROD	5.5	6850	0	WITH 1450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/27/2010 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: BUD NEFF, PRODUCTIONS S Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: CIBP @ 5200' WITH 2 SX CMT. PLUG AT 1850' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2010 2:30 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

CIBP @ 5190' WITH 2 SX CMT. 1ST PLUG AT 1850' WITH 60 SX CMT. 2ND PLUG AT 650' WITH 70 SX CMT. FILLED TO SURFACE. PUMPED 45 SX CMT DOWN BACKSIDE. PRESSURED TO 350 PSI.

Perfs:

Top	Bot	Thru	Comments
6758	6770		ST. LOUIS
5270	5276		MARMATON

DATE: 12/07/10
NO. 2011060309

RECEIVED
NOV 08 2010
KCC WICHITA

RECEIVED
OCT 28 2010
KCC DODGE CITY

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Jack Macclashy
(TECHNICIAN)