

\$ 110.79

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20771-00-00
Spot: SWNENW Sec/Twnshp/Rge: 6-20S-1W
4324 feet from S Section Line, 3610 feet from E Section Line
Lease Name: GRACE WALN Well #: 1
County: MCPHERSON Total Vertical Depth: 3409 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		
PROD	5.5	3409		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/19/2010 12:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: TRAVIS HAMM Company: _____ Phone: (620) 628-4424

Proposed Plugging Method: AS PER KKCC RULES AND REGULATIONS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/25/2010 10:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

10/20/10 AMERICAN ENERGIES DROPPED SAND. 10/21/10 AMERICAN ENERGIES TAGGED SAND @ 2810' AND CAPPED W/ 5 SX. THEY THEN RAN 1" DOWN BACKSIDE TAGGING @ 300'. GOAL WAS TO GET TO 450'. THEY RAN 2" DOWN TO 450' INSIDE THE 5.5". 10/22/10 COPELAND TIED ON TO THE 1" AND AMERICAN ENERGIES TRIED TO WASH DOWN TO 450". THEY DID NOT MAKE ANY GROUND SO WILL CIRCULATE BACKSIDE FROM 300'. COPELAND PUMPED 100 SXS DOWN 1" TO CIRCULATE TO SURFACE. THEY THEN TIED ON TO THE 2" AND BROKE CIRCULATION WITH WATER. ONCE HAD CIRCULATION SWITCHED TO CEMENT AND CIRCULATED 50 SXS TO SURFACE. AMERICAN ENERGIES THEN PULLED THE 1" TUBING. IT PARTED ON THE TOP COLLAR. SO THERE IS A 300' OF 1" TUBING CEMENTED IN ON THE BACKSIDE. AMERICAN ENERGIES THEN PULLES THE 2", AND COPELAND TOPPED OFF THE 5.5" WITH ANOTHER 20 SXS. CEMENT STILL FALLING. TK # 36645 USED 170 SXS 60/40 POS W/4% GEL. I WENT BACK BY THE WELL TO GET A GPS READING AND COULD NOT SEE CEMENT IN THE 5.5". I DROPPED A ROCK AND FOUND FLUID APPROX 550' DOWN. I NOTIFIED TRAVIS W/AMERICAN ENERGIES. THEY WILL GO BACK AND CHECK LATER THIS AFTERNOON. TRAVIS LET ME KNOW PLAN TO REDO TOP PLUG MONDAY MORNING. 10/25/10 AMERICAN ENERIGES RAN TUBING IN AND TAGGED @ 550'. THEY PULLED UP TO 450'. COPELAND TIED ON AND BROKE CIRCULATION WITH WATER. THEY THEN SWITCHED TO CEMENT, AND CIRCULATED 75 SXS 60/40 POS W/4% GEL TO SURFACE TK #35156. THEY PULLED TUBING HOLE STANDING FULL. 10/26/2010 CHECKED TOP PLUG AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3299	3300	CSG	

Inv. #: 2011060285
Inv. dt: 12/15/10


Remarks:
Plugged through: TBG

RECEIVED
NOV 03 2010

KCC WICHITA

District: 02

Signed



(TECHNICIAN)

SK