

\$ 120.25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23107-00-00  
Spot: NESWSENE Sec/Twnshp/Rge: 13-7S-22W  
2150 feet from N Section Line, 800 feet from E Section Line  
Lease Name: ESTHER WORCESTER Well #: 1-13  
County: GRAHAM Total Vertical Depth: 3700 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213	0	150 SX CMT
T1	2.875	3694		
PROD	5.5	3687	0	440 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2010 9:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JIM BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls - 14 sxs gel spacer.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/30/2010 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls - 14 sxs gel spacer - followed with 210 sxs 60/40 pozmix - 4% gel and 200# hulls. Well was on a slight vacuum. Topped off 5 1/2" casing with 20 sxs 60/40 pozmix - 4% gel. Hooked to 8 5/8" x 5 1/2" annulus - pumped 10 sxs 60/40 pozmix - 4% gel to bring to surface.

Perfs:

Top	Bot	Thru	Comments
3687	3700		

INVOICED  
DATE 12/07/10  
SERV. NO. 2011060291

Remarks: SWIFT SERVICES, INC.-TICKET #18119.

Plugged through: CSG

District: 04

Signed Pat Bedore  
(TECHNICIAN) CM

RECEIVED

OCT 08 2010

KCC WICHITA

OCT 04 2010