

#117.0

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19109-00-00
Spot: E2SWSWNE Sec/Twnshp/Rge: 8-15S-18W
2310 feet from N Section Line, 1995 feet from E Section Line
Lease Name: RUDER C Well #: 3
County: ELLIS Total Vertical Depth: 3614 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	236	0	160 SX
PROD	4.5	3606	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2010 1:10 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Revd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method:	Ordered 260 sxs 60/40 pozmix - 4% gel - 500# hulls - 8 sxs gel. DV at 1196' w/425 sxs. CIBP 3552'. April 1964-squeezed 518' w/200 sxs. Well is broke in - fluids to surface. Emergency plug with rig over the hole-ok from Case Morris-Supervisor.
---------------------------	---

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2010 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling RIH with tubing to 3500'.
Quality Oil Well rigged to tubing and pumped 6 sxs gel - followed with 50 sxs 60/40 pozmix with 200# hulls mixed in.
Pulled tubing to 1900'. Quality Oil Well rigged to tubing and pumped 80 sxs cement with 200# hulls.
Pulled tubing to 700'. Quality Oil Well rigged to tubing and pumped 50 sxs cement with 100# hulls to circulate cement to pit area.
Pulled tubing and rigged to 4 1/2" casing - pumped 10 sxs cement to top off. Hole standing full. Rigged to 8 5/8" casing. Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3606	3614		ARBUCKLE O.H.
DATE <u>12/07/10</u>			
WV. NO. <u>2011060308</u>			
RECEIVED OCT 19 2010 KCC WICHITA			

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4334.
Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

OCT 18 2010