

145.02

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21678-00-00
Spot: NESWNWSW Sec/Twnshp/Rge: 10-21S-25W
1861 feet from S Section Line, 606 feet from W Section Line
Lease Name: RONALD-BRIAN "B" Well #: 1-10
County: HODGEMAN Total Vertical Depth: 4462 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	223		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/21/2010 1:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1620' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 10/21/2010 3:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG AT 1620' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED

Plugged through: DP

District: 01

Signed _____

Jerry W Stapleton
PIR #

(TECHNICIAN)

RECEIVED

OCT 22 2010

KCC DODGE CITY

INVOICE
DATE 12/07/10
INV. NO. 2011060286

RECEIVED

OCT 27 2010

KCC WICHITA

