

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20173-00-00
Spot: SESWSW Sec/Twnshp/Rge: 16-14S-10W
322 feet from S Section Line, 4309 feet from E Section Line
Lease Name: SOUKUP A Well #: 2
County: ELLSWORTH Total Vertical Depth: 2950 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2815		
SURF	8.625	239		150 SX
PROD	4.5	2948		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/03/2010 1:30 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: SET CIBP AT 2790 AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1200', 850', AND 290'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 850' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 290' AND CIRCULATE CEMENT TO SURFACE. NO PERFS LISTED ON CP-1, OBTAINED THAT INFO FROM KEN BUEHLER.

Plugging Proposal Received By: B. J. HOPE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2010 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPT TO RUN WIRELINE TO BOTTOM - ENCOUNTERED BLOCKAGE AT 1484'. RUN NOTCHED TUBING DOWN - GOT THRU BLOCKAGE AND ON DOWN TO TAG CIBP THAT HAD PREVIOUSLY BEEN SET AT 2815'. PULLED TUBING UP TO 2784' AND PUMPED 15 SX'S CEMENT WITH 3% CALCIUM. PULL TUBING TO JUST ABOVE 1200'. RUN SLIM GUN THRU TUBING, PERFOATE AT 1200'. PULL GUN OUT- LOWER TUBING TO 1200' AND PUMP 23 SX'S CEMENT. PULL TUBING JUST ABOVE 850' - RUN SLIM GUN TO 850' - PERFOATE AND PULL GUN OUT. LOWER TUBING BACK TO 850' AND PUMP 35 SX'S CEMENT. PULL TUBING TO JUST ABOVE 290' - RUN SLIM GUN TO 290' - PERFORATE AND PULL GUN OUT OF HOLE. LOWER TUBING BACK DOWN TO 290', AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON 4.5" CASING AND PUMP CEMENT UP SURFACE CASING. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2840	2863	CSG	

RECEIVED
AUG 17 2010
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. PERF TECH TICKET #7396. QUALITY WELL CEMENT TICKET #4130.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)