

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-01056-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 20-28S-5W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ALTHOUSE A Well #: 1  
County: KINGMAN Total Vertical Depth: 3940 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260		165 SX
PROD	5.5	3939	3164	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE INC Phone: (620) 938-2537

Proposed Plugging Method: PER KCC DISTRICT 2 INSTRUCTIONS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/04/2010 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP WAS ALREADY IN BOREHOLE @ 3890'. 8/2/10 SANDE DBACK TO 3785' CAPPED WITH 5 SKS OF CEMENT. 8/3/10-CUT CASING OFF AT 3164' PULLED CASING TO 918' SPOTTED 35 SXS OF CEMENT. PULLED CASING TO 325' CIRCULATED TO SURFACE WITH 160 SXS OF CEMENT. FELL BACK 60'--TOPPED WITH 15 SXS OF CEMENT

Perfs:

Top	Bot	Thru	Comments
3899	3910	CSG	MISS DOLOMITE
3876	3888	CSG	MISS CHERT

Remarks: COPELAND OUT OF GREAT BEND - TICKET #34792-60/40 4% GEL

Plugged through: CSG

District: 02

Signed B. J. Hope  
(TECHNICIAN)

RECEIVED  
SEP 27 2010  
KCC WICHITA