

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22976-00-00  
Spot: SENE5W Sec/Twnshp/Rge: 15-24S-14W  
1632 feet from S Section Line, 2276 feet from W Section Line  
Lease Name: SUITER Well #: 2  
County: STAFFORD Total Vertical Depth: 4147 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	271		WITH 190 SX CMT
PROD	4.5	4148	2020	WITH 115 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2010 12:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3950' & 4 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/01/2010 2:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BACK TO 3950' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 50' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4046	4052		MISS CHERT

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

*Richard M. Lacey*

(TECHNICIAN)

RECEIVED  
NOV - 9 2010  
KCC DODGE CITY

RECEIVED  
NOV 15 2010  
Form CD 2/3

KCC WICHITA