

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21465-00-00
Spot: NESESW Sec/Twnshp/Rge: 2-30S-22W
980 feet from S Section Line, 2420 feet from W Section Line
Lease Name: MCCAUSTLAND Well #: 1
County: CLARK Total Vertical Depth: 5475 feet

Operator License No.: 31514
Op Name: THOROUGHbred ASSOCIATES L.L.C.
Address: 8100 E 22ND ST STE 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5300		WITH 2 SX CMT
SURF	8.625	730		WITH 200 SX CMT
PROD	4.5	5469	2900	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2010 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 5300' WITH 2 SX CMT. PLUG AT 1440' WITH 15 SX GEL & 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 390' WITH 30 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/01/2010 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5300' WITH 2 SX CMT. 1ST PLUG AT 1440' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 768' WITH 50 SX CMT. 3RD PLUG AT 384' WITH 30 SX CMT. 4TH PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5353	5358		

INVOICED
DATE 12/03/10
INV. NO. 2011060244

RECEIVED
JUL 21 2010

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.
Plugged through: DP

KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JUL 14 2010
KCC DODGE CITY

Form CP 2/3