

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08553-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 9-15S-13W
328 feet from S Section Line, 2091 feet from E Section Line
Lease Name: ROESNER Well #: 10
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 9250 E COSTILLA AVE #510
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	616	0	325 SX
PROD 7		3053	0	300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2010 9:00 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 16 sxs gel.
Perf: 1500' - 840' - 600' - 150'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2010 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2804' - pumped 16 sxs gel - followed with 75 sxs cement with 200# hulls.
Pulled tubing to 1500' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 850' - pumped 130 sxs cement - cement circulated.
Filled casing with 10 sxs cement.
POOH. Hooked up to Braden head and pumped 5 sxs cement.
Max. P.S.I. 75#. Cement circulated out casing.

Perfs:

Top	Bot	Thru	Comments
3053	3080		
3043	3047		
3016	3021		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKE #4549.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN) *CM*

RECEIVED

OCT 12 2010

Form CP-2/3

OCT 07 2010

KCC WICHITA