

5/26.26

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-03114-00-01  
Spot: SENWNWNE Sec/Twnshp/Rge: 30-9S-22W  
4638 feet from S Section Line, 2088 feet from E Section Line  
Lease Name: FARRELL A Well #: 1W  
County: GRAHAM Total Vertical Depth: 3885 feet

Operator License No.: 30537  
Op Name: VENTURE RESOURCES, INC.  
Address: 2255 S WADSWORTH, STE 205  
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	189	0	w/unknown sxs cmt
PROD	4.5	3885	0	w/unknown sxs cmt

Well Type: EOR UIC Docket No: E22217.1 Date/Time to Plug: 06/28/2010 10:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN CURLEY Company: VENTURE RESOURCES, INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Perf 1222' w/197 sxs.  
3 1/2" liner set at 3787' w/190 sxs cement.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/28/2010 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Tied onto 4 1/2" - pumped 190 sxs cement with 600# hulls.  
S.I.P. 500#.  
Tied onto backside - pumped 110 sxs cement - no pressure - ordered more cement.  
Tied back on the backside - pumped 50 sxs cement.  
S.I.P. 50#.

*Inv. dt: 12/15/10*  
*Inv. #: 2011060256*

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 02 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT SERVICES, INC.-TICKET #17669.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

JUL 01 2010

~~IMPERIAL OIL CO~~

#1 FARRELL

30-9-22W  
C NW NE

Contr. IMPERIAL OIL

GRAHAM

County

E 2387 RB Comm.

Comp. 2-9-62

IP 91 BOPD/LANS

Tops	Depth	Datum
ANH	1927	+460
HEEB	3619	-1232
TOR	3640	-1253
LANS	3654	-1267
TD	3885	-1498

Casing

8" 189

4" 3885

DST 3648-77/2 HRS, 360' W, BHP 1175#

DST 3774-3805/2 HRS, 1125' W, BHP 1120#

DST 3803-19/30", 15' SL OCM, BHP 60#

DST 3835-58/30", 10' M, BHP 935#

PERF 20/3811-16: ACID 1750: SWB @ RATE  
OF 180 BOPD

RED LINE NW POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS