

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26032-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 35-13S-20W
3010 feet from S Section Line, 341 feet from E Section Line
Lease Name: J A ENGEL Well #: 6
County: ELLIS Total Vertical Depth: 3866 feet

Operator License No.: 5798
Op Name: WEILERT, MICHAEL D. DBA MICHAEL
Address: 866 230TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	233		

Well Type: DH UIC Docket No: . Date/Time to Plug: 10/20/2010 8:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 10/20/2010 9:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


1st. Plug at 3820' w/25 sxs.
2nd. Plug at 1544' w/25 sxs.
3rd. Plug at 798' w/100 sxs.
4th. Plug at 283' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED Form CP-2/3

OCT 25 2010

KCC WICHITA

OCT 21 2010