

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25045-00-00
Spot: W2NW Sec/Twnshp/Rge: 29-20S-21W
1135 feet from N Section Line, 345 feet from W Section Line
Lease Name: BELTZ Well #: 3
County: NESS Total Vertical Depth: 4395 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	253		WITH 175 SX CMT
PROD	5.5	4395	815	WITH 150 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/15/2010 10:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILTON PETROLEUM Phone: (620) 628-4466

Proposed Plugging Method: SAND TO 4295' WITH 5 SX CMT. SET CIBP @ 1450' WITH 2 SX CMT. PLUG AT 650' WITH 60 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/15/2010 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

LEFT 716' OF CASING IN HOLE AT 1441' TO 725'. SANDED TO 4312' & 5 SX CMT. SHOT CASING OFF AT 1531' & PUMPED 50 SX CMT. COULDN'T PULL CASING. SHOT CASING OFF AT 725' THEN CEMENTED AT 650' WITH 60 SX CMT. PULLED CASING TO 280' CEMENTED WITH 50 SX CMT. PULLED CASING OUT OF HOLE & TOPPEED OFF WITH 30 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4353	4354		
4345	4346		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG


RECEIVED

OCT 22 2010

KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED

OCT 19 2010

KCC DODGE CITY

Form CP-2/3