

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20355-00-00
Spot: W2SW Sec/Twnshp/Rge: 36-17S-31W
1342 feet from S Section Line, 4599 feet from E Section Line
Lease Name: SCOTT E Well #: 2
County: SCOTT Total Vertical Depth: 4590 feet

Operator License No.: 7775
Op. Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3920		WITH 2 SX CMT
SURF	8.625	275		WITH 275 SX CMT
PC		2306		WITH 480 SX CMT
PROD	4.5	4589	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2010 1:00 PM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: RENE Company: H-D OILFIELD SERVICE, INC. Phone: (785) 398-2289

Proposed Plugging Method: SAND TO 3920' & 4 SX CMT. PLUG AT 22310' CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2010 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3920' WITH 2 SX CMT. RUN TBG TO 2310'. CIRCULATED CMT TO SURFACE WITH 175 SX CMT. TOOH WITH TBG. TOP OFF 4 1/2" CASING WITH 14 SX CMT. PUMP 10 SX CMT DOWN ANNULUS. SHUT IN PRESSURE 400#.

Perfs:

Top	Bot	Thru	Comments
4346	4352		
4251	4253		
3972	3980		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED
JUL 23 2010

KCC WICHITA

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

RECEIVED

JUL 13 2010 *MP*

KCC DODGE CITY