

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21768-00-01
Spot: SWSWNENE Sec/Twnshp/Rge: 6-27S-31W
4049 feet from S Section Line, 1249 feet from E Section Line
Lease Name: MATHES B Well #: 11-6
County: HASKELL Total Vertical Depth: 3160 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	555		WITH 280 SX CMT
PROD	5.5	3153	0	WITH 525 SX CMT
RBP		2787		WITH 2 BAGS SAND

Well Type: EOR UIC Docket No: D30178.0 Date/Time to Plug: 08/03/2010 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: RUN TBG TO 1900' & FILL WITH CMT. CHECK 8 5/8" X 5 1/2" WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2010 11:00 AM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

RBP @ 2787' WITH SAND ON TOP. CMT TO 1929'. PUMP 190 SX CMT FROM 1925' TO SURFACE. TIED ONTO 5 1/2" & 8 5/8" ANNULUS & PUMP 7 SX CMT. MAXIMUM PRESSURE 350#.

Perfs:

Top	Bot	Thru	Comments
2646	2661		

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacClaskey
(TECHNICIAN)

RECEIVED

AUG - 6 2010

KCC DODGE CITY

RECEIVED

AUG 16 2010

KCC WICHITA