

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21086-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 22-21S-21W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: BLOUNT Well #: 6
County: HODGEMAN Total Vertical Depth: 4316 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1278		WITH 525 SX CMT
PROD	5.5	4314	1850	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2010 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAIME HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SAND TO 4260' WITH 5 SX CMT. PLUG AT 1290' WITH 15 SX GEL - 200# HULLS - 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 07/01/2010 11:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 4260' & 5 SX CMT. 1ST PLUG AT 1290' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 660' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4314	4316		MISS OH
4309	4313		MISS

RECEIVED
JUL 28 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED

JUL 22 2010

KCC DODGE CITY

Signed

Jerry W Stapleton
PART 4

(TECHNICIAN)

Form CP-23