

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23768-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 19-20S-12W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: DEWERFF Well #: 3-19  
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	301	0	200 SX
PROD	4.5	3582	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/07/2010 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: VESS OIL CORPORATION Phone: (620) 562-8088

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Bad casing starting out at 75'. Ran tubing to 1600' - ran outside casing.  
Tubing stacked out. Started plugging from there.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/07/2010 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1590' and 690'.  
Tied to tubing at 1590' - pumped 75 sxs cement.  
Pulled to 675' - pumped 225 sxs cement - circulated cement to surface.  
Pulled tubing - tied onto casing - pumped 25 sxs cement - circulated cement out surface pipe.  
Shut in.  
Checked plug 07/08/2010 - casing full of cement.

Perfs:

Top	Bot	Thru	Comments
3506	3510		ARBUCKLE
3502	3509		ARBUCKLE
3491	3494		ARBUCKLE - SQU
3482	3486		ARBUCKLE
3474	3479		ARBUCKLE

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36547.

Plugged through: CSG

District: 04

RECEIVED *Bruce Rodie*  
(TECHNICIAN) *CM*

JUL 19 2010

KCC WICHITA

JUL 13 2010

TEXAS ENERGIES, INC.  
P.O. BOX 947


#3-19 DEWERFF

19-20-12W  
NW SE SW

PRATT, KS 67124

CONTR WHEATSTATE OILFIELD SVC. CTY BARTON

GEOL RICHARD HARPER FIELD BATCHMAN SW



ELV 1852 KB SPD 11/9/84 CARD ISSUED 2/14/85 IP P 20 BO & 15 BWPD  
1847 GL ARB 3474-3486 OA

LOG	Tops	Depth/Datum
ANH	.....	665+1187
HEEB	.....	3067-1215
TOR	.....	3087-1235
DOUG	.....	3104-1252
BR LM	.....	3191-1339
LANS	.....	3207-1355
CONG	.....	3441-1589
ARB	.....	3466-1614
PBTD	.....	3575-1723
RTD	.....	3600-1748
LTD	.....	3609-1757

API 15-009-23,768

8 5/8 " 301 / 200SX, 4 1/2 " 3482 / 150SX

DST (1) 3318-3340 (LANS H) / 30-30-30-30, REC 6' M, W/RBSO, SIP 36-29#, FP 24-24 / 24-24#, HP 1755-1731#

DST (2) 3459-3495 (ARB) / 30-45-45-60, 707' GIP, REC 124' VHOOM, 372' V SL MCO, 186' MCO, SIP 940-905#, FP 72-181 / 181-241#, HP 1826-1802#

DST (3) 3495-3510 (ARB) / 30-45-45-60, 738' GIP, REC 20' CL GSY OIL, 372' MCO, SIP 963-882#, FP 95-119 / 154-178#, HP 1907-1849#

DST (4) 3510-3520 (ARB) / 30-45-30-60, REC 62' OIL SPKD M, W / OIL ON TOP OF TOOL, SIP 1105-1105#, FP 72-60 / 72-60#, HP 1919-1872#

MICT - CO, PF (ARB) 3506-3510, W / 2 SPF, AC 500G, SWB DWN, NS, PF (ARB) 3491-3494, W / 2 SPF, AC 500G, SWB DWN, NS, SQZ'D (3491-3494) W/58SX, CHANNELED & SQZ'D (3506-3510) W/CMT, CO CMT, PF (ARB) 3474-79 & 3482-86, W / 2 SPF, AC 500G, SWB DWN, GSO, T&R, POP, P 20 BO & 15 BWPD, 12/21/84

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS