

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03105-00-00
Spot: NWNENE Sec/Twnshp/Rge: 28-16S-11W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: ESFELDE F Well #: 3
County: BARTON Total Vertical Depth: 3335 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 9250 E COSTILLA AVE #510
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	739	0	300 SX
PROD	5.5	3329	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2010 9:00 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 525 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 400' - 730' - 1400'.
Ran tubing to 3250' - pumped 13 sxs gel - followed with 60 sxs cement and 200# hulls.
Pulled to 1400' - pumped 75 sxs cement with 200# hulls.
Pulled to 730' - circulated to surface with 290 sxs cement - circulated casing and surface pipe.
Pulled all tubing - topped off with 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3329	3335		
3075	3134		

Remarks: QUALITY OIL WELL CEMENTING-TICKET #5044.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

RECEIVED Form CP-2/3

NOV 17 2010

KCC WICHITA

NOV 15 2010