

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-12794-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 31-21S-12W  
996 feet from S Section Line, 3638 feet from E Section Line  
Lease Name: FISCHER J K Well #: 3  
County: STAFFORD Total Vertical Depth: 3622 feet

Operator License No.: 33699  
Op Name: T-N-T ENGINEERING, INC.  
Address: 3711 MAPLEWOOD STE 201  
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	236		WITH 165 SX CMT
PROD	5.5	3618	1410	WITH 100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/30/2010 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICKEY POPP Company: T-N-T ENGINEERING Phone: (620) 786-5514

Proposed Plugging Method: SAND TO 3260' WITH 5 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/30/2010 3:07 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 3620' WITH 5 SX CMT. 1ST PLUG @ 700' WITH 10 SX GEL, 50# HULLS & 50 SX CMT. 2ND PLUG AT 260' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT. CMT CIRCULATED BUT FELL AFTER PUMPING STOPPED. TOPPED OFF WITH 30 SX CMT. 8/31/10: TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3618	3622		ARB
3445	3452		LKC
3408	3416		LKC
3367	3371		LKC
3355	3358		LKC
3311	3314		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
AUG 31 2010  
KCC DODGE CITY

RECEIVED  
SEP 07 2010  
KCC WICHITA