

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05467-00-00
Spot: SESESE Sec/Twnshp/Rge: 9-15S-13W
328 feet from S Section Line, 405 feet from E Section Line
Lease Name: ROESNER Well #: 1
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	318	0	110 SX
LI	5.5	3315	0	50 SX
PROD	7	3073	0	70 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2010 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 700# hulls - 600# c.c.
Perf: 1500' - 825'.
Casing squeezed at an earlier date at 360' to 404' - cement circulated to surface.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2010 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2530' - pumped 100 sxs cement with 3% c.c. - followed with 150 sxs cement with 450# hulls.
Pulled tubing to 1200' - pumped 225 sxs cement with 250# hulls - cement circulated.
POOH. Hooked up to casing and pumped 25 sxs cement.
Max. P.S.I. 200#.
Braden head was full of cement.

Perfs:

Top	Bot	Thru	Comments
3474	3480		
3315	3340		
3274	3277		
3262	3266		
3236	3238		
3230	3232		
3217	3219		
3210	3212		
3192	3196		
3150	3154		
3138	3142		
3125	3130		
3056	3072		
3040	3042		
2980	2990		
2493	2496		
2482	2485		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4190.

Plugged through: TBG

RECEIVED

SEP 03 2010

KCC WICHITA

District: 04

Signed Ray A. Dinkel

(TECHNICIAN)

CM

AUG 31 2010

STANOLIND O & G CO

#1

ROESNER

9-15-13W

SE SE SE

Contr.

RUSSELL

County

E 1868

Comm.

5-8-36

Comp.

6-26-36

IP

500 BOPD

Tops	Depth	Datum
ANHY	815	
FT R	1760	
TOP	2710	
LANS	3041	
ARB	3315	
TD	3340	

Casing
 10" 318
 7" 3071

SSO 3057-59
 3½ EW 3100-09
 1 BOPH 3121-23
 SSO 3190
 291' 5" lnr @ 3315
 SSO 3327-29
 3000' OIH/1 hr
 SW 3338-40

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS