

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19177-00-01
Spot: N2NWSW Sec/Twnshp/Rge: 9-15S-13W
2317 feet from S Section Line, 4669 feet from E Section Line
Lease Name: ROESNER Well #: 6
County: RUSSELL Total Vertical Depth: 3325 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3306		
SURF	10.75	616	0	375 SX
PROD	7	3315	0	300 SX

Well Type: EOR UIC Docket No: E07604.2 Date/Time to Plug: 09/01/2010 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls - 15 sxs gel.
Perf: 1500' - 825' - 200'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2010 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2900' - pumped 15 sxs gel - followed with 50 sxs cement with 200# hulls.
Pulled tubing to 1500' - pumped 125 sxs cement with 200# hulls.
Pulled tubing to 700' - pumped 135 sxs cement - cement circulated.
POOH. Hooked to casing - pumped 75 sxs cement.
Max. P.S.I. 600#.
Cement circulated out the Braden head.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3311	3325		
3080	3086		
3063	3072		
3056	3080		
2981	2988		
2911	2914		

RECEIVED
SEP 08 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4191.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

SEP 02 2010

STANOLIND OIL & GAS

#6

R. ROESNER

9-15-13W / 33
N2 NW SW

Contr. _____ RUSSELL County

E 1871 Comm. _____ Comp. 11-17-50 IP 33 BOPD & 51 BW

Tops	Depth	Datum
LANS	3030	-1159
ARB	3315	-1444
T.D.	3325	-1454

Casing

OLD WELL W0
 OLD T.D. 3325
 SQZ OLD LANS PERS.
 CO 3325
 33 B0 & 51 BW/24 HRS
 FROM ARBUCKLE

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS