

#114.89

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21267-00-00
Spot: N2SEW Sec/Twnshp/Rge: 12-20S-6W
1650 feet from N Section Line, 1980 feet from W Section Line
Lease Name: SWENSON Well #: 1
County: RICE Total Vertical Depth: 3535 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 247 | | 200 sxs |
| PROD | 5.5 | 3521 | 1400 | 300 sxs |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2010 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 10/14/2010 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:
MIRU, CK BOTTOM. SAND PERFS TO 3290' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 1400' AND PULL TO 850' AND PUMP 35 SX'S CEMENT. PULL CASING TO 450' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT AND TOP OFF. USED 240 SX'S CEMENT.

Perfs:
INVOICED
DATE 12/07/10
INV. NO. 2011060304

RECEIVED
NOV 02 2010
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. QUALITY WELL CEMENT TICKET #5086

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK