

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20355-00-00  
Spot: E2W2NE Sec/Twnshp/Rge: 30-32S-40W  
3960 feet from S Section Line, 1470 feet from E Section Line  
Lease Name: MONTGOMERY A Well #: 2-30  
County: MORTON Total Vertical Depth: 2750 feet

Operator License No.: 8294  
Op Name: STROMQUIST, C. DALE, A GENERAL P  
Address: 1210 N. PROSPECT  
LIBERAL, KS 67901

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2490		WITH 2 SX CMT
SURF	8.625	624		WITH 375 SX CMT
PROD	5.5	2745	830	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/23/2010 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: RODNEY GONZALES Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/23/2010 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 2490' WITH 2 SX CMT. PERFORATE HOLES @ 1500'. 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. NO CIRCULATION. SHUT DOWN 3 HOURS TO WAIT ON CMT. TAGGED TOC @ 700'. POOH TO 660'. PUMPED 75 SX CMT. GOOD CIRCULATION. HELD OK. PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2548	2654		

*Inv. dt: 12/3/10*  
*Inv. #: 2011060238*

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED  
SEP 01 2010  
KCC WICHITA

District: 01

RECEIVED  
AUG 26 2010  
KCC DODGE CITY

Signed Jack MacLaskey  
(TECHNICIAN)