

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23424-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 26-34S-11W
1212 feet from S Section Line, 1759 feet from E Section Line
Lease Name: BROWN/ROLFE UNIT Well #: 1-26
County: BARBER Total Vertical Depth: 5170 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 200 W DOUGLAS AVE STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4625		WITH 2 SX CMT
SURF	8.625	731		WITH 200 SX CMT
COND	13.38	80		WITH 115 SX CMT
PROD	5.5	4830	3121	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/17/2011 12:00 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: CIBP @ 4625' WITH 2 SX CMT. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: PARTIAL
Date/Time Plugging Completed: 02/17/2011 7:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4625' WITH 2 SX CMT. 1ST PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 35' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4693	4699		MISSISSIPPI
4678	4682		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

RECEIVED
FEB 23 2011
KCC WICHITA

District: 01

RECEIVED
FEB 18 2011
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP 2/3