

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22499-00-00
Spot: E2NWSWNW Sec/Twnshp/Rge: 9-26S-5E
3683 feet from S Section Line, 4906 feet from E Section Line
Lease Name: FINNEY 2 Well #: 43
County: BUTLER Total Vertical Depth: 2469 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	259		150 sxs
PROD	4.5	2434		250 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/06/2011 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2011 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2430', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL, 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 2140'. RIH W/TBG @ 310', CONSOLIDATED ESTABLISHED CIRCULATION AND PUMPED 45 SXS 60/40 POXMIX 4% GEL TO SURFACE. LAYED DOWN TBG, SWEDGED INTO 4-1/2" CASING AND PUMPED ANOTHER 10 SXS. SHUT IN W/PRESSURE. CEMENT CIRCULATED. PLUG DOWN 11:00 AM, 1-6-2011, CONSOLIDATED CEMENT TICKET #30827.

Perfs:

Top	Bot	Thru	Comments
2440	2450	OH	Arbuckle OH

Remarks: CEMENT @ SURFACE ON BACKSIDE OF 4-1/2" PRODUCTION CASING

Plugged through: TBG

RECEIVED
FEB 02 2011
KCC WICHITA

District: 02

Signed



(TECHNICIAN)