

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20553-00-01
Spot: NWSENE Sec/Twnshp/Rge: 7-23S-11W
3660 feet from S Section Line, 1020 feet from E Section Line
Lease Name: MINNIS Well #: 2
County: STAFFORD Total Vertical Depth: 3794 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	286		WITH 225 SX CMT
PROD	4.5	3694	900	WITH 150 SX CMT

Well Type: SWD UIC Docket No: D18381.0 Date/Time to Plug: 02/04/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 02/04/2011 11:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

RAN 3600' OF TBG WITH 50 SX CMT W/ 200# HULLS. 1ST PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3695	3794		Arb OH
3467	3470		
3452	3455		
3435	3438		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed

Jerry W. Stapleton
PIRT, II (TECHNICIAN)

RECEIVED
FEB 14 2011
KCC DODGE CITY

RECEIVED
FEB 14 2011
2-18-11
KCC WICHITA

Form CP-23

cc to MIC