

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23647-00-00  
Spot: NWSESWNW Sec/Twnshp/Rge: 26-10S-25W  
2275 feet from N Section Line, 989 feet from W Section Line  
Lease Name: KNOLL Well #: A-1  
County: GRAHAM Total Vertical Depth: 4091 feet

Operator License No.: 30259  
Op Name: WERTH, ANDY DBA WERTH EXPLORA  
Address: 1308 SCHWALLER AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	233	0	150 SX
PROD	4.5	4090	2532	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/23/2010 9:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: ANDY WERTH / JOHN BEC Company: WERTH EXPLORATION TRUST Phone: (785) 625-4968

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Spotted 300' sand and 4 sxs cement on bottom.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/23/2010 1:30 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Shot 4 1/2" casing off at 2532' - pulled to 2100' - pumped 160 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled 4 1/2" casing to 1200' - pumped 80 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled 4 1/2" casing to 280' - pumped 105 sxs 60/40 pozmix - 4% gel to circulate to surface.  
Pulled 4 1/2" casing to surface. Topped off with 10 sxs 60/40 pozmix - 4% gel.

**Perfs:**

Top	Bot	Thru	Comments
3790	3945		

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35087.

Plugged through: CSG

RECEIVED  
DEC 30 2010  
12-30-10  
KCC WICHITA

District: 04

Signed \_\_\_\_\_

*Pat Bedore*  
(TECHNICIAN)

CM

Form CP-2/3

DEC 29 2010