

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21770-00-00
Spot: NESENE Sec/Twnshp/Rge: 2-18S-27W
3544 feet from S Section Line, 315 feet from E Section Line
Lease Name: BROWN Well #: 1
County: LANE Total Vertical Depth: 4575 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		WITH 150 SX CMT
PC		2001		WITH 565 SX CMT
PROD	4.5	4234	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2010 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JASON Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: RIHWT TO 4100' & PUMP 200# HULLS & 25 SX CMT. PTT TO 2020' & PUMP 30 SX CMT. PTT TO 1350' CIRCULATE CMT TO 0'.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/23/2010 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT WITH 15 BALL SEALERS @ 4150'. PULL TBG TO 2080' & LOAD THE 4 1/2" CASING WITH 59 BBLs WATER. PUMP 30 SX CMT AT 2080' WITH PARTIAL RETURNS. PUMP 95 SX CMT AT 1250' IN 2 STAGES WITH NO RETURNS. TOO H W/TBG. PUMP 8 SX CMT DOWN ANNULUS TO 150#. PUMP 60 SX CMT DOWN 4 1/2" CASING WITH NO RETURNS. 12/23/10: TOPPED OFF WELL WITH 40 SX CMT DOWN 630'.

Perfs:

Top	Bot	Thru	Comments
4148	4152		

RECEIVED
DEC 30 2010

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

KCC WICHITA

Plugged through: TBG

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
DEC 28 2010
KCC DODGE CITY

Form CR-2/3