

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21662-00-00  
Spot: N2SEW Sec/Twnshp/Rge: 15-29S-32W  
3661 feet from S Section Line, 3277 feet from E Section Line  
Lease Name: RICKETTS Well #: 1  
County: HASKELL Total Vertical Depth: 5642 feet

Operator License No.: 33036  
Op Name: STRATA EXPLORATION, INC.  
Address: PO BOX 401  
FAIRFIELD, IL 62837

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5470		WITH 2 SX CMT
SURF	8.625	1751		WITH 750 SX CMT
PC		3618		WITH 250 SX CMT
PROD	5.5	5640	0	WITH 175 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/28/2011 8:30 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: SHANE PELTON Company: STRATA EXPLORATION Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP @ 5470' WITH 2 SX CMT. PERFORATE AT 1780' & PUMP 50 SX CMT. PERFORATE AT 720' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/28/2011 3:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5470' WITH 2 SX CMT. PERFORATE 5 1/2" AT 1780' & PUMP 50 SX CMT. PERFORATE 5 1/2" CASING AT 720' & CIRCULATE 80 SX CMT FILL 5 1/2" & 8 5/8" ANNULUS & 5 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
5538	5542		
5522	5530		

RECEIVED  
MAR 30 2011  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
MAR 29 2011  
KCC DODGE CITY