

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00606-00-00
Spot: NENESE Sec/Twnshp/Rge: 32-5S-20W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: RAY A Well #: 4
County: PHILLIPS Total Vertical Depth: 3600 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 162 | 0 | 125 SX |
| PROD | 5.5 | 3576 | 0 | 100 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2011 12:30 PM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8036

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perfed at 1700' and 210'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2011 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3392' - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1960' - pumped 200 sxs 60/40 pozmix - 4% gel with 225# hulls to circulate to surface.
Hooked to 8 5/8" x 5 1/2" annulus - pumped 30 sxs 60/40 pozmix - 4% gel - circulated cement to surface in 5 1/2" casing.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 3576 | 3600 | | REAGAN SAND |

RECEIVED
MAR 23 2011
KCC WICHITA

Remarks: SWIFT CEMENTING COMPANY-TICKET #19621.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

MAR 21 2011