

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01992-00-00
Spot: NENESW Sec/Twnshp/Rge: 1-10S-20W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SUTOR A Well #: 5-5
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	161	0	100 SX
PROD	5.5	3745	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2011 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 562-8104

Proposed Plugging Method: Ordered 485 sxs 60/0 pozmix - 4% gel - 500# hulls.
Casing leak at 1700' - decided to P/A. No Alt II records.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2011 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 1680' - and 1000'.
Ran tubing to 3400'. Allied pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 2782' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1762' - pumped 110 sxs cement - circulated.
PTOH. Allied squeezed 45 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Hooked up to backside and pumped 50 sxs cement with 150# hulls.
Max. P.S.I. 100#. S.I.P. 0#. Backside full.

Perfs:

Top	Bot	Thru	Comments
3785	3800		Open hole
3650	3654		
3574	3578		
3431	3435		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

RECEIVED

MAR 24 2011

Form CP-2/3

KCC WICHITA

MAR 22 2011