

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21837-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 3-30S-32W  
1250 feet from S Section Line, 1254 feet from E Section Line  
Lease Name: LONGBOTHAM Well #: 3-3  
County: HASKELL Total Vertical Depth: 2993 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2600		WITH 2 SX CMT
SURF	8.625	690		WITH 350 SX CMT
PROD	4.5	2983	0	WITH 435 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2011 9:00 AM  
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC  
Proposal Rcvd. from: TONY ANTON Company: OXY USA Phone: \_\_\_\_\_

Proposed Plugging Method: CIBP @ 2600' WITH 2 SX CMT. PLUG AT 1400' WITH 25 SX CMT. FILL 4 1/2" FROM 700' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 03/25/2011 11:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

\*\*BOND LOG TOC @ 350.\*\* SET CIBP @ 2600' WITH 2 SX CMT. 1ST PLUG AT 1400' WITH 25 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT TO SURFACE. PUMP 40 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURED TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
2816	2823		
2768	2777		
2724	2733		
2687	2695		
2658	2664		

RECEIVED  
MAR 31 2011  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Steve Durrant  
(TECHNICIAN)

RECEIVED  
MAR 30 2011  
KCC DODGE CITY