

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-04168-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 9-20S-9W
4626 feet from S Section Line, 1668 feet from E Section Line
Lease Name: MILLER Well #: 3
County: RICE Total Vertical Depth: 3232 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	206		100 SX
PROD 7		3226	1200	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2010 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed SEE BELOW
Plugging
Method:

Plugging Proposal Received By: DAVID BOLLENBACK WitnessType: PARTIAL
Date/Time Plugging Completed: 08/16/2010 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3175' AND CAP WITH 10 SX'S CEMENT. CUT CASING AT 1200' AND PULL OUT OF HOLE. RUN TUBING TO 1175' AND PUMP 50 SX'S CEMENT WITH 3% CALCIUM AND COTTON HULLS. PULL TUBING TO 775' AND PUMP 50 SX'S CEMENT WITH 3% CALCIUM AND COTTON HULLS. PULL TUBING TO 256' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3225	3232		ARBUCKLE

Remarks: 60-40 POZ, 4% GEL. QUALITY WELL CEMENT #5056.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED

Form CP-2/3

AUG 19 2010

KCC WICHITA