

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01673-00-00
Spot: E2SENWNW Sec/Twnshp/Rge: 6-18S-10W
990 feet from N Section Line, 1314 feet from W Section Line
Lease Name: AMES W R Well #: 6
County: RICE Total Vertical Depth: 3241 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3241		
SURF	8.625	206		100 SX
PROD	6	3235		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/07/2010 9:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 09/07/2010 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CP-1 INDICATES POOR WELL CONDITION-CK BOTTOM. PERFORATE @ 1250', 900', & 260'. RUN TUBING TO 2700' & PUMP 15 SX'S GEL, & 500#'S COTTON HULLS, & 75 SX'S CEMENT. PERFORATE @ 1250', 900', & 260'. RUN TUBING TO 1250' & PUMP 100 SXS CEMENT - NO CIRCULATION, SHUT DOWN. COME BACK ON 9-7-2010 - TAG CEMENT @ 1200'. PUMP 100 SX'S CEMENT & 500 #'S COTTON HULLS - DID GET CIRCULATION. PULLED TUBING TO 900' & PUMPED 75 SX'S CEMENT & 25 SX'S GEL WITH 550 #'S COTTON HULLS, & 3% CALCIUM CHLORIDE. CASING WENT ON VACUUM. PULLED 2 JTS. TUBING - CASING STARTED GASSING BACK. PUMPED 450 #'S COTTON HULLS & 25 SX'S GEL - NO CIRCULATION. BUILD PLUG - PUSH DOWN TO 900' & MAKE A ROCK BRIDGE ON TOP OF, THEN PUMPED 75 SX'S CEMENT @ 870' - GOT GOOD CIRCULATION. PULL TUBING TO 260' & CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT & TOP OFF. PUMP 100 SX'S CEMENT DOWN BACK SIDE OF CASING. RE-CK'D ON 9-9-2010 - CEMENT @ SURFACE ON BACKSIDE - TOOK 20 SX'S TO TOP OFF PRODUCTION CASING.

Perfs:

Top	Bot	Thru	Comments
3234	3241		ARBUCKLE OPEN

Remarks: 60-40 POZ, 4% GEL & COTTON HULLS - WENT ON VACUUM. COPELAND TICKET #C35101

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
SEP 23 2010
KCC WICHITA